



EROSION & SEDIMENT CONTROL MEASURES:

- ALL TEMPORARY STOCKPILES WILL BE COVERED WITH 6 MIL PLASTIC SHEETING WHICH IS ANCHORED SUITABLY TO PREVENT DISRUPTION DURING HIGH WIND EVENTS.
- ALL DRIVEWAY AND CONSTRUCTION ACCESS ROADS SHALL BE GRAVEL SURFACED AND MAINTAINED IN GOOD CONDITION.
- ALL OTHER EXPOSED BARE GROUND SHALL BE COVERED WITH MULCHING, JUTE MAT, OR OTHER EROSION CONTROL BLANKETS.
- SITE MONITORING WILL BE CONDUCTED BY THE CONTRACTOR BEFORE AND AFTER SIGNIFICANT RAINFALL EVENTS TO VERIFY THAT THE EROSION CONTROL MEASURES ARE SATISFACTORY.
- DISTURBED VEGETATED AREAS WILL BE REVEGETATED.
- ALL EROSION CONTROL MATERIAL SHALL BE ONSITE OR READILY ACCESSIBLE PRIOR TO CONSTRUCTION FOR INSTALLATION DUE TO UNTIMELY WET WEATHER.

SITE NOTES:

- NO (E) TREES TO BE REMOVED;
- NO (P) GRADING;
- NO PERENNIAL & INTERMITTENT WATER COURSES LOCATED ON SITE;
- NO (P) OR (E) CURBS, SIDEWALKS, OR GUTTERS;
- NO PROPANE OR KEROSENE STORAGE TANKS.

REVISIONS

#	DATE	DESCRIPTION

OWNER:
JOEL GECK-MOELLER
P.O. BOX 688
LOLETA, CA 95551
707.273.0528
loletagm@gmail.com

SHEET DATE: 12.11.2023
DRAWN BY: CAT ORY

SHEET NO.
A-1.1
GECK-MOELLER RESIDENCE